BRUHAT BENGALURU MAHANAGARA PALIKE

Name of work:-Improvements to widen portion of roads, construction of new drains, UG cable duct and footpath at Doddabommasandra main road and surrounding road in Ward No.10

60

SL. No	Description of Itmes	Unit	No	L(m)	B(m)	D(m)	Qty	Rate	Amount
	ASPHALT ROAD								
1	KSRRB M300-14. **Excavation for roadwork** in all types of soil with hydraulic excavator of 0.9 cum bucket capacity including cutting and loading in tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transporting to the embankment location to a lead of 1.00 km and complete as per specifications. MORTH Specification No.301(pg no-143,S.Lno-19.14)KPWD SR 2018-19								
		Cum							
	Vidyaranyapura near underground								
	3rd cross road (W0809)		1	205.00	4.50	0.30	276.75		
	4th cross road (W0811)		1	198.00	5.20	0.30	308.88		
	5th cross road (W0813) Only for Trench Cutting Portion		1	206.00	6.80	0.30	420.24		
	Road opp to Narayana hospital		1	72.00	5.80	0.30	125.28		
	kaveri street								
	4th cross road (new road)		1	132.00	5.90	0.30	233.64		
	3rd main road (for berm portion)		2	262.00	0.50	0.30	78.60		
	1st main road (for trench cut portion, from 4th crosss)		1	170.00	1.50	0.30	76.50		
	for trench cut								
	2nd cross (gas godown road)		1	182.00	1.00	0.30	54.60		
							1574.49	**125.59**	**197,738.31**
	Basic Rate	41.00							
	Loading & Unloading	57.00							
	Add for Lead of earth (1.28 Tonne/ Cum) 8km	20.48							
	Area Weightage @ 6 %	7.11							
	Total Rate	125.59							
2	Construction of granular sub-base Grading-V as sub-base and drainage layer by providing coarse graded crushed stone aggregates of granite/trap/basalt material, mixing in a mechanical mix plant at OMC, carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98% proctor density, complete as per specifications. Clause 401 of MORTH V Revision.GSB Page No. 153/ Item No. 20.5/ PWD SR 2018-19								
		Cum							
	Vidyaranyapura near underground								
	3rd cross road (W0809)		1	205.00	4.50	0.20	184.50		
	4th cross road (W0811)		1	198.00	5.20	0.20	205.92		
	5th cross road (W0813) Only for Trench Cutting Portion		1	206.00	6.80	0.25	350.20		
							740.62	**1994.92**	**1,477,477.65**
	Basic Rate	1882.00							
	Area Weightage @ 6 %	112.92							
	Total Rate	1994.92							
3	KSRRB M400-17. Providing, laying, spreading and compacting crushed stone aggregates of granite / trap / basalt to **wet mix macadam** specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH Specification No. 406 Page No. 155/ Item No. 20.18/ PWD SR 2018-19								
		Cum							

VSR CIVIL INFRA PVT LTD

BRUHAT BANGALORE MAHANAGARA PA

SL. No	Description of Itmes	Unit	No	L(m)	B(m)	D(m)	Qty	Rate	Amount
	Vidyaranyapura near underground								59
	3rd cross road (W0809)		1	205.00	4.50	0.23	212.18		
	4th cross road (W0811)		1	198.00	5.20	0.23	236.81		
	5th cross road (W0813) Only for Trench Cutting Portion		1	206.00	6.80	0.23	322.18		
	Road opp to Narayana hospital		1	72.00	5.80	0.23	96.05		
	kaveri street								
	4th cross road (new road)		1	132.00	5.90	0.23	179.12		
	3rd main road (for berm portion)		2	262.00	0.50	0.23	60.26		
	1st main road (for trench cut portion, from 4th crosss)		1	170.00	1.50	0.23	58.65		
	for trench cut								
	2nd cross (gas godown road)		1	182.00	1.00	0.23	41.86		
	Basic Rate	1888.00					**1207.11**	**2001.28**	**2,415,763.10**
	Area Weightage @ 6 %	113.28							
	Total Rate	2001.28							
4	KSRRB M500-6. Providing and applying **primer coat** with S.S. bitumen emulsion on prepared surface of granular base such as WMM ,including clearing of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per Specifications. MORTH Specification No. 502 Complete with all lead and lift and as per the direction of the Engineer-in-Charge. Page No. 158/ Item No. 21.6/ PWD SR 2018-19 Issue Rates								
		Sqm							
	Vidyaranyapura near underground								
	3rd cross road (W0809)		1	205.00	4.50		922.50		
	4th cross road (W0811)		1	198.00	5.20		1029.60		
	5th cross road (W0813) Only for Trench Cutting Portion		1	206.00	6.80		1400.80		
	Road opp to Narayana hospital		1	72.00	5.80		417.60		
	Dhanalakshmi Layout								
	Road opp to helios Enclave		1	60.70	5.50		333.85		
	Intermidiate Road		1	53.20	5.40		287.28		
	Road opp to Mother's Delight		1	28.00	5.30		148.40		
	Road towards NISH 9 Apartments		1	70.10	5.70		399.57		
	kaveri street								
	4th cross road (new road)		1	132.00	5.90		778.80		
	3rd main road (for berm portion)		1	262.00	5.80		1519.60		
	1st main road (for trench cut portion, from 4th crosss)		1	170.00	5.90		1003.00		
	For profile correction								
	vidyaranyapura ramswamappa layout								
	2nd cross road		1	54.50	4.50		245.25		
	3rd cross road		1	35.70	4.70		167.79		
	1st main road		1	155.60	4.90		762.44		
	Byrappa garden								
	2nd cross road		1	186.20	5.10		949.62		
	krishna temple main road		1	139.40	4.20		585.48		
	Main road (chamundeshwari temple road)		1	160.00	5.90		944.00		
	main road (renukamba temple road)		1	236.00	4.90		1156.40		
	3rd C cross road		1	92.70	4.10		380.07		
	2nd B cross road		1	77.00	4.40		338.80		
	2nd A cross road		1	55.00	4.30		236.50		

VSR CIVIL INFRA PVT LTD

BRUHAT BANGALORE MAHANAGARA PALIKE

SL. No	Description of Itmes	Unit	No	L(m)	B(m)	D(m)	Qty	Rate	Amount
	Ramaiah garden								
	2nd B cross road		1	115.00	6.00		690.00		
	2nd main road		1	190.00	6.00		1140.00		
	Deshabandhu nagara(yarappa garden)								
	2nd main road		1	177.00	5.80		1026.60		
	3rd main road		1	90.00	4.50		405.00		
	4th main road		1	156.00	4.50		702.00		
	1st B cross road		1	51.00	4.20		214.20		
	5th main road		1	166.40	6.30		1048.32		
	1st cross(mukabika farm house		1	74.00	4.50		333.00		
	7th main road		1	200.00	4.60		920.00		
	8th main road		1	134.00	4.40		589.60		
	11th main road		1	222.40	5.40		1200.96		
	2nd cross road		1	74.70	4.80		358.56		
	1st cross road(family enclave)		1	109.70	6.20		680.14		
	3rd cross road		1	98.00	4.60		450.80		
	3rd A cross road		1	87.00	4.50		391.50		
	3rd C cross road		1	49.00	5.00		245.00		
	Doddabommasandra main road		1	1250.00	9.70		12125.00		
	1st phase muniswamappa layout		1	76.00	4.50		342.00		
	1st main chikkavenkatappa layout		1	134.00	5.00		670.00		
	2nd b cross ramaiah layout		1	65.00	4.80		312.00		
	2nd cross (gas godown road)		1	182.00	5.00		910.00		
							38762.03	**29.68**	**1,150,457.05**
	Basic Rate	28.00							
	Area Weightage @ 6 %	1.68							
	Total Rate	29.68							
5	KSRRB M500-17. Providing and laying **dense graded bituminous macadam** using crushed aggregates of specified grading, premixed with VG30 grade bituminous binder and, transporting the hot mix to work site, laying to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH table 500-10 complete in all respects complete as per specifications. Clause 505 of morth V revision using 40/60 TPH capacity H.M.P. with mechanical paver Gr-II (50mm to 75mm) with 4.5% VG-30 Bitumen. Page No. 160/ Item No. 21.17.6/ PWD SR 2018-19 Issue Rates								
		Cum							
	Vidyaranyapura near underground								
	3rd cross road (W0809)		1	205.00	4.50	0.05	46.13		
	4th cross road (W0811)		1	198.00	5.20	0.05	51.48		
	5th cross road (W0813) Only for Trench Cutting Portion		1	206.00	6.80	0.05	70.04		
	Road opp to Narayana hospital		1	72.00	5.80	0.05	20.88		
	Dhanalakshmi Layout								
	Road opp to helios Enclave		1	60.70	5.50	0.05	16.69		
	Intermidiate Road		1	53.20	5.40	0.05	14.36		
	Road opp to Mother's Delight		1	28.00	5.30	0.05	7.42		
	Road towards NISH 9 Apartments		1	70.10	5.70	0.05	19.98		
	kaveri street								
	4th cross road (new road)		1	132.00	5.90	0.05	38.94		
	3rd main road (for berm portion)		1	262.00	0.50	0.05	6.55		
	1st main road (for trench cut portion, from 4th crosss)		1	170.00	1.50	0.05	12.75		

VSR CIVIL INFRA PVT LTD BANGALORE

SL. No	Description of Itmes	Unit	No	L(m)	B(m)	D(m)	Qty	Rate	Amou
	For profile correction								
	vidyaranyapura ramswamappa layout								
	2nd cross road		1	54.50	0.90	0.05	2.45		
	3rd cross road		1	35.70	0.94	0.05	1.68		
	1st main road		1	155.60	0.98	0.05	7.62		
	Byrappa garden						0.00		
	2nd cross road		1	186.20	1.02	0.05	9.50		
	krishna temple main road		1	139.40	0.84	0.05	5.85		
	Main road (chamundeshwari temple road)		1	160.00	1.18	0.05	9.44		
	main road (renukamba temple road)		1	236.00	0.98	0.05	11.56		
	3rd C cross road		1	92.70	0.82	0.05	3.80		
	2nd B cross road		1	77.00	0.88	0.05	3.39		
	2nd A cross road		1	55.00	0.86	0.05	2.37		
	Ramaiah garden						0.00		
	2nd B cross road		1	115.00	1.20	0.05	6.90		
	2nd main road		1	190.00	1.20	0.05	11.40		
	Deshabandhu nagara(yarappa garden)								
	2nd main road		1	177.00	1.16	0.05	10.27		
	3rd main road		1	90.00	0.90	0.05	4.05		
	4th main road		1	156.00	0.90	0.05	7.02		
	1st B cross road		1	51.00	0.84	0.05	2.14		
	5th main road		1	166.40	1.26	0.05	10.48		
	1st cross(mukabika farm house		1	74.00	0.90	0.05	3.33		
	7th main road		1	200.00	0.92	0.05	9.20		
	8th main road		1	134.00	0.88	0.05	5.90		
	11th main road		1	222.40	1.08	0.05	12.01		
	2nd cross road		1	74.70	0.96	0.05	3.59		
	1st cross road(family enclave)		1	109.70	1.24	0.05	6.80		
	3rd cross road		1	98.00	0.92	0.05	4.51		
	3rd A cross road		1	87.00	0.90	0.05	3.92		
	3rd C cross road		1	49.00	1.00	0.05	2.45		
	Doddabommasandra main road		1	1250.00	3.88	0.05	242.50		
	1st phase muniswamappa layout		1	76.00	1.80	0.05	6.84		
	1st main chikkavenkatappa layout		1	134.00	1.00	0.05	6.70		
	2nd b cross ramaiah layout		1	65.00	0.96	0.05	3.12		
	2nd cross (gas godown road)		1	182.00	1.00	0.05	9.10		
							735.10	**6407.70**	**4,710,302.19**
	Basic Rate	6045.00							
	Area Weightage @ 6 %	362.70							
	Total Rate	6407.70							
6	KSRRB 500-2. **Cleaning the existing black** topped surface with brooms, soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries complete as per specifications. MORTH specification clause 501 Page No. 158/ Item No. 21.2/ PWD SR 2018-19								
		Sqm							
	Vidyaranyapura near underground								
	3rd cross road (W0809)		1	205.00	4.50		922.50		
	4th cross road (W0811)		1	198.00	5.20		1029.60		
	5th cross road (W0813) Only for Trench Cutting Portion		1	206.00	6.80		1400.80		
	Road opp to Narayana hospital		1	72.00	5.80		417.60		
	Dhanalakshmi Layout								

VSR CIVIL INFRA PVT LTD

BRUHAT BANGALORE MAHANAGARA PA

SL. No	Description of Itmes	Unit	No	L(m)	B(m)	D(m)	Qty	Rate	Amount
	Road opp to helios Enclave		1	60.70	5.50		333.85		
	Intermidiate Road		1	53.20	5.40		287.28		
	Road opp to Mother's Delight		1	28.00	5.30		148.40		
	Road towards NISH 9 Apartments		1	70.10	5.70		399.57		
	kaveri street								
	4th cross road (new road)		1	132.00	5.90		778.80		
	3rd main road (for berm portion)		1	262.00	5.80		1519.60		
	1st main road (for trench cut portion, from 4th crosss)		1	170.00	5.90		1003.00		
	vidyaranyapura ramswamappa layout						0.00		
	2nd cross road		1	54.50	4.50		245.25		
	3rd cross road		1	35.70	4.70		167.79		
	1st main road		1	155.60	4.90		762.44		
	Byrappa garden						0.00		
	2nd cross road		1	186.20	5.10		949.62		
	krishna temple main road		1	139.40	4.20		585.48		
	Main road (chamundeshwari temple road)		1	160.00	5.90		944.00		
	main road (renukamba temple road)		1	236.00	4.90		1156.40		
	3rd C cross road		1	92.70	4.10		380.07		
	2nd B cross road		1	77.00	4.40		338.80		
	2nd A cross road		1	55.00	4.30		236.50		
	Ramaiah garden						0.00		
	2nd B cross road		1	115.00	6.00		690.00		
	2nd main road		1	190.00	6.00		1140.00		
	Deshabandhu nagara(yarappa garden)								
	2nd main road		1	177.00	5.80		1026.60		
	3rd main road		1	90.00	4.50		405.00		
	4th main road		1	156.00	4.50		702.00		
	1st B cross road		1	51.00	4.20		214.20		
	5th main road		1	166.40	6.30		1048.32		
	1st cross(mukabika farm house		1	74.00	4.50		333.00		
	7th main road		1	200.00	4.60		920.00		
	8th main road		1	134.00	4.40		589.60		
	11th main road		1	222.40	5.40		1200.96		
	2nd cross road		1	74.70	4.80		358.56		
	1st cross road(family enclave)		1	109.70	6.20		680.14		
	3rd cross road		1	98.00	4.60		450.80		
	3rd A cross road		1	87.00	4.50		391.50		
	3rd C cross road		1	49.00	5.00		245.00		
	Doddabommasandra main road		1	1250.00	9.70		12125.00		
	1st phase muniswamappa layout		1	76.00	4.50		342.00		
	1st main chikkavenkatappa layout		1	134.00	5.00		670.00		
	2nd b cross ramaiah layout		1	65.00	4.80		312.00		
	2nd cross (gas godown road)		1	182.00	5.00		910.00		
							38762.03	**5.30**	**205,438.76**
	Basic Rate	5.00							
	Area Weightage @ 6 %	0.30							
	Total Rate	5.30							

VSR CIVIL INFRA PVT LTD

BRUHAT BANGALORE MAHANAGARA PALIK

SL. No	Description of Itmes	Unit	No	L(m)	B(m)	D(m)	Qty	Rate	Amount
7	KSRRB 500-7. Providing and applying **tack coat** using 80/100 grade bitumen(VG10) on the prepared black topped surfaces at 2.5 kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specifications. MORTH/Chapter 5 Page No. 158/ Item No. 21.7/ PWD SR 2018-19 Issue Rates								55
		Sqm							
	Vidyaranyapura near underground								
	3rd cross road (W0809)		1	205.00	4.50		922.50		
	4th cross road (W0811)		1	198.00	5.20		1029.60		
	5th cross road (W0813) Only for Trench Cutting Portion		1	206.00	6.80		1400.80		
	Road opp to Narayana hospital		1	72.00	5.80		417.60		
	Dhanalakshmi Layout								
	Road opp to helios Enclave		1	60.70	5.50		333.85		
	Intermidiate Road		1	53.20	5.40		287.28		
	Road opp to Mother's Delight		1	28.00	5.30		148.40		
	Road towards NISH 9 Apartments		1	70.10	5.70		399.57		
	kaveri street				0.00				
	4th cross road (new road)		1	132.00	5.90		778.80		
	3rd main road (for berm portion)		1	262.00	5.80		1519.60		
	1st main road (for trench cut portion, from 4th crosss)		1	170.00	5.90		1003.00		
	vidyaranyapura ramswamappa layout								
	2nd cross road		1	54.50	4.50		245.25		
	3rd cross road		1	35.70	4.70		167.79		
	1st main road		1	155.60	4.90		762.44		
	Byrappa garden								
	2nd cross road		1	186.20	5.10		949.62		
	krishna temple main road		1	139.40	4.20		585.48		
	Main road (chamundeshwari temple road)		1	160.00	5.90		944.00		
	main road (renukamba temple road)		1	236.00	4.90		1156.40		
	3rd C cross road		1	92.70	4.10		380.07		
	2nd B cross road		1	77.00	4.40		338.80		
	2nd A cross road		1	55.00	4.30		236.50		
	Ramaiah garden				0.00				
	2nd B cross road		1	115.00	6.00		690.00		
	2nd main road		1	190.00	6.00		1140.00		
	Deshabandhu nagara(yarappa garden)								
	2nd main road		1	177.00	5.80		1026.60		
	3rd main road		1	90.00	4.50		405.00		
	4th main road		1	156.00	4.50		702.00		
	1st B cross road		1	51.00	4.20		214.20		
	5th main road		1	166.40	6.30		1048.32		
	1st cross(mukabika farm house		1	74.00	4.50		333.00		
	7th main road		1	200.00	4.60		920.00		
	8th main road		1	134.00	4.40		589.60		
	11th main road		1	222.40	5.40		1200.96		
	2nd cross road		1	74.70	4.80		358.56		
	1st cross road(family enclave)		1	109.70	6.20		680.14		
	3rd cross road		1	98.00	4.60		450.80		
	3rd A cross road		1	87.00	4.50		391.50		
	3rd C cross road		1	49.00	5.00		245.00		

VSR CIVIL INFRA PVT LTD BANGALORE

SL No	Description of Itmes	Unit	No	L(m)	B(m)	D(m)	Qty	Rate	Amount
	Doddabommasandra main road		1	1250.00	9.70		12125.00		
	1st phase muniswamappa layout		1	76.00	4.50		342.00		
	1st main chikkavenkatappa layout		1	134.00	5.00		670.00		
	2nd b cross ramaiah layout		1	65.00	4.80		312.00		
	2nd cross (gas godown road)		1	182.00	5.00		910.00		
							38762.03	**12.72**	**493,053.02**
	Basic Rate	12.00							
	Area Weightage @ 6 %	0.72							
	Total Rate	12.72							
8	KSRRB M500-19. Providing and laying **bituminous concrete** using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications. Clause 507 of MORTH V revision. -using40/60 TPH capacity H.M.P. with Mechanical Paver Gr-II (30 mm to 40 mm) with 5.4% VG-30 Bitumen (Pg:162, It.No-21.22.6 PWD SR:2018-19)Issue Rates								
		Cum							
Vidyaranyapura near underground									
	3rd cross road (W0809)		1	205.00	4.50	0.04	36.90		
	4th cross road (W0811)		1	198.00	5.20	0.04	41.18		
	5th cross road (W0813) Only for Trench Cutting Portion		1	206.00	6.80	0.04	56.03		
	Road opp to Narayana hospital		1	72.00	5.80	0.04	16.70		
	Dhanalakshmi Layout								
	Road opp to helios Enclave		1	60.70	5.50	0.04	13.35		
	Intermidiate Road		1	53.20	5.40	0.04	11.49		
	Road opp to Mother's Delight		1	28.00	5.30	0.04	5.94		
	Road towards NISH 9 Apartments		1	70.10	5.70	0.04	15.98		
	kaveri street								
	4th cross road (new road)		1	132.00	5.90	0.04	31.15		
	3rd main road (for berm portion)		1	262.00	5.80	0.04	60.78		
	1st main road (for trench cut portion, from 4th crosss)		1	170.00	5.90	0.04	40.12		
	vidyaranyapura ramswamappa layout								
	2nd cross road		1	54.5	4.50	0.04	9.81		
	3rd cross road		1	35.7	4.70	0.04	6.71		
	1st main road		1	155.6	4.90	0.04	30.50		
	Byrappa garden								
	2nd cross road		1	186.20	5.10	0.04	37.98		
	krishna temple main road		1	139.40	4.20	0.04	23.42		
	Main road (chamundeshwari temple road)		1	160.00	5.90	0.04	37.76		
	main road (renukamba temple road)		1	236.00	4.90	0.04	46.26		
	3rd C cross road		1	92.70	4.10	0.04	15.20		
	2nd B cross road		1	77.00	4.40	0.04	13.55		
	2nd A cross road		1	55.00	4.30	0.04	9.46		
	Ramaiah garden								
	2nd B cross road		1	115.00	6.00	0.04	27.60		
	2nd main road		1	190.00	6.00	0.04	45.60		
	Deshabandhu nagara(yarappa garden)								
	2nd main road		1	177.00	5.80	0.04	41.06		

VSR CIVIL INFRA PVT LTD

BRUHAT BANGALORE MAHANAGARA PALIK

SL. No	Description of Itmes	Unit	No	L(m)	B(m)	D(m)	Qty	Rate	Amount
	3rd main road		1	90.00	4.50	0.04	16.20		
	4th main road		1	156.00	4.50	0.04	28.08		
	1st B cross road		1	51.00	4.20	0.04	8.57		
	5th main road		1	166.40	6.30	0.04	41.93		
	1st cross(mukabika farm house		1	74.00	4.50	0.04	13.32		
	7th main road		1	200.00	4.60	0.04	36.80		
	8th main road		1	134.00	4.40	0.04	23.58		
	11th main road		1	222.40	5.40	0.04	48.04		
	2nd cross road		1	74.70	4.80	0.04	14.34		
	1st cross road(family enclave)		1	109.70	6.20	0.04	27.21		
	3rd cross road		1	98.00	4.60	0.04	18.03		
	3rd A cross road		1	87.00	4.50	0.04	15.66		
	3rd C cross road		1	49.00	5.00	0.04	9.80		
	Doddabommasandra main road		1	1250.00	9.70	0.04	485.00		
	1st phase muniswamappa layout		1	76.00	4.50	0.04	13.68		
	1st main chikkavenkatappa layout		1	134.00	5.00	0.04	26.80		
	2nd b cross ramaiah layout		1	65.00	4.80	0.04	12.48		
	2nd cross (gas godown road)		1	182.00	5.00	0.04	36.40		
							1550.48	**7355.34**	**11,404,316.39**
	Basic Rate	6939.00							
	Area Weightage @ 6 %	416.34							
	Total Rate	7355.34							
9	KSRRB M800-13.**Road Marking** with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface:- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. MORTH Specification No. 803 Page No. 182/ Item No. 24.15 PWD SR 2018-19								
		Sqm							
Vidyaranyapura near underground									
	3rd cross road (W0809)		2	205.00	0.10		41.00		
	4th cross road (W0811)		2	198.00	0.10		39.60		
	5th cross road (W0813) Only for Trench Cutting Portion		2	206.00	0.10		41.20		
	Road opp to Narayana hospital		2	72.00	0.10		14.40		
	Dhanalakshmi Layout								
	Road opp to helios Enclave		2	60.70	0.10		12.14		
	Intermidiate Road		2	53.20	0.10		10.64		
	Road opp to Mother's Delight		2	28.00	0.10		5.60		
	Road towards NISH 9 Apartments		2	70.10	0.10		14.02		
	kaveri street								
	4th cross road (new road)		2	132.00	0.10		26.40		
	3rd main road (for berm portion)		2	262.00	0.10		52.40		
	1st main road (for trench cut portion, from 4th crosss)		2	170.00	0.10		34.00		
	vidyaranyapura ramswamappa layout								
	2nd cross road		2	54.50	0.10		10.90		
	3rd cross road		2	35.70	0.10		7.14		
	1st main road		2	155.60	0.10		31.12		
	Byrappa garden								
	2nd cross road		2	186.20	0.10		37.24		
	krishna temple main road		2	139.40	0.10		27.88		

SL. No	Description of Itmes	Unit	No	L(m)	B(m)	D(m)	Qty	Rate	Amount
	Main road (chamundeshwari temple road)		2	160.00	0.10		32.00		
	main road (renukamba temple road)		2	236.00	0.10		47.20		
	3rd C cross road		2	92.70	0.10		18.54		
	2nd B cross road		2	77.00	0.10		15.40		
	2nd A cross road		2	55.00	0.10		11.00		
	Ramaiah garden								
	2nd B cross road		2	115.00	0.10		23.00		
	2nd main road		2	190.00	0.10		38.00		
	Deshabandhu nagara(yarappa garden)								
	2nd main road		2	177.00	0.10		35.40		
	3rd main road		2	90.00	0.10		18.00		
	4th main road		2	156.00	0.10		31.20		
	1st B cross road		2	51.00	0.10		10.20		
	5th main road		2	166.40	0.10		33.28		
	1st cross(mukabika farm house		2	74.00	0.10		14.80		
	7th main road		2	200.00	0.10		40.00		
	8th main road		2	134.00	0.10		26.80		
	11th main road		2	222.40	0.10		44.48		
	2nd cross road		2	74.70	0.10		14.94		
	1st cross road(family enclave)		2	109.70	0.10		21.94		
	3rd cross road		2	98.00	0.10		19.60		
	3rd A cross road		2	87.00	0.10		17.40		
	3rd C cross road		2	49.00	0.10		9.80		
	Doddabommasandra main road		2	1250.00	0.10		250.00		
	1st phase muniswamappa layout		2	76.00	0.10		15.20		
	1st main chikkavenkatappa layout		2	134.00	0.10		26.80		
	2nd b cross ramaiah layout		2	65.00	0.10		13.00		
	2nd cross (gas godown road)		2	182.00	0.10		36.40		
							1270.06	**454.74**	**577,547.08**
	Basic Rate	429.00							
	Area Weightage @ 6 %	25.74							
	Total Rate	454.74							

10	KSRRB M800 Road markers / Road stud KSRRB M800-35. Providing and fixing of road stud 100x 100 mm, diecast in aluminium, resistant to corrosive effect of salt and grit, fitted with lense reflectors, installed in concrete or asphaltic surface by drilling hole 30 mm upto a depth of 60 mm and bedded in a suitable bituminous grout or epoxy mortar, all as per BS: 873 part 4:1973 complete as per specifications Page No. 186/ Item No. 24.41 PWD SR 2018-19								
		Nos							
	For center marking								
	Doddabommasandra main road		1	1250.00			1250.00		
	Total Length						**1250.00**		
	Total Length / 2.0M						**625.00**	**357.22**	**223,262.50**
	For side marking								
	Doddabommasandra main road		2	1250.00			2500.00		
	Total Length						**2500.00**		
	Total Length / 5.0M						**500.00**	**357.22**	**178,610.00**
	Basic Rate	337.00							
	Area Weightage @ 6 %	20.22							
	Total Rate	357.22							

VSR CIVIL INFRA PVT LTD BANGALORE

SL. No	Description of Itmes	Unit	No	L(m)	B(m)	D(m)	Qty	Rate	Amount
								Sub Total-A	23,033,966.06
								Tender Premium 5%	1,151,698.30
								GST 12%	2,764,075.93
								DPR 1%	275,000.00
								PMC 1%	275,000.00
								Miscellaneous	259.71
								Total	27,500,000.00

51

Technical Sanction
Accorded For Rs 275.00 Lakhs
Head of A/C ... D-3089
CER NO : ... Dt:..
TA CE (YNK)

VSR CIVIL INFRA PVT. LTD. BANGALORE
Consultant

Asst Executive Engineer
Project Yelahanka

Assistant Engineer
Ward No. 19

Executive Engineer
Project Yelahanka

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Administrative Approval
Accorded For Rs. 275.00 Lakhs
Head of A/C D 3089
CER NO : 01 Dt: 15/05/2021
E.E. (Project)

Technical Sanction
Accorded For Rs 275.00 Lakhs only
Head of A/C D3089
CER NO : 89 Dt: 10.08.2020
TA CE (YNK)